

**UNITED STATES DISTRICT COURT
EASTERN DISTRICT OF PENNSYLVANIA
PROBATION OFFICE**

**RONALD DeCASTRO
CHIEF U.S. PROBATION OFFICER**

**FEDERAL OFFICE BUILDING
600 ARCH STREET, SUITE 2400
PHILADELPHIA, PA 19106-1679
215-597-7950
FAX # 215-597-8856**

August 1, 2012

Request for Open Market Pricing

RFQ Number: 2012-PAEP-001
Request Date: August 1, 2012

This is a request for Open Market Pricing

Quotes may be faxed or emailed with company letterhead to the below listed address by **August 10, 2012, at 12:00 Noon, Eastern Daylight Time**. However, hand carried quotes are to be delivered by the same time at **600 Arch Street, Suite 2400, Philadelphia, PA, 19106, Attention: Procurement and Financial Specialist**.


Submit a technical proposal describing your approach and project management in accordance with the attached statement of work. Use the attached quote sheet for a price quotation broken down by task with any supporting documentation for the price attached. Award will be made by August 20, 2012.

A fixed price award from the RFQ will be made based on the lowest priced, technically acceptable offer.

Quotes and questions concerning this RFQ should be addressed to Enid Valentin at U.S. Probation Office, ED/PA, 600 Arch Street, Suite 2400, Philadelphia, PA, 19106. Phone Number: 267-299-4608, Fax Number 215-597-8856, E-mail Address: enid_valentin@paep.uscourts.gov.

The address for this project will be: William J. Green Jr., Federal Building, 600 Arch Street, Suite 2400, Philadelphia, PA 19106.

Sincerely,



Ronald DeCastro
Contracting Officer

Pennsylvania Eastern Probation Office

Probation Office - Second Floor Green Building Cabling Proposal:

Scope of Work:

Contractor will install the following.

1. Install 135 locations consisting of 1 Cat6 plenum data cable.
2. Install 25 locations consisting of 2 Cat6 plenum data cable.
3. Install 10 locations consisting of 3 Cat6 plenum data cable.
4. All new cat 6 cabling will be terminate on new 48 port Cat6 patch panels in the new equipment rack.
5. Install 01 new floor mount equipment rack.
6. Install up to 10' of 12' ladder tray.
7. Install 02 new 4' cores and sleeves.
8. Test, certify and label all new cabling.

Materials:

51,000	ft.	Cat6 Plenum Data Cable
225	ea.	Cat6 Jacks
170	ea.	Face Plates
05	ea.	48 Port Cat6 Patch Panel
01	ea.	Floor Mount Equipment Rack
10	ft.	12' Ladder Tray W/ Hardware
75	ea.	J Hooks and Cable Support
02	ea.	4" Sleeves
01	ft.	Fire Stop Consumables

Labor \$ _____

Material \$ _____

Total = \$ _____